


- NOTES:
1. ALL MATERIAL TO MEET SPECIFICATIONS.
 2. SEDIMENT SHOULD BE REMOVED FROM BEHIND CHECK DAM ONCE THE ACCUMULATED HEIGHT HAS REACHED 1/2 THE HEIGHT OF THE CHECK DAM.
 3. CHECK DAM CAN BE DIRECT SEEDED AT THE TIME OF INSTALLATION.
 4. FILTER MEDIA FILL TO MEET APPLICATION REQUIREMENTS.
 5. COMPOST MATERIAL TO BE DISPERSED ON SITE, AS DETERMINED BY ENGINEER.

SEDIMENT SOCK
 C### NTS

Revisions:

No.	Date:	Description:

Graphic Scale	
DFD Number	
Set Type	
Date Issued	8/1/2017
Sheet Number	