PLACEMENT

s. 236.15 (1)(ac), Wis. Stats. Monuments must be placed flush with the ground at all:

- Exterior boundary corners and angle points, meander corners and angle points, and curve PCs and PTs;
- Interior block, street right-of-way, curve PCs and PTs and angle points;
- Lot and outlot corners, angle points, and curve PCs and PTs:
- Meander corners and angle points, and at the intersections of lot lines and meander lines.

When an exterior boundary corner, angle point, or curve P.C / P.T. falls within a street in a subdivision plat, the monument is set along the right-of-way line.

Meander corner monuments must be set 20 feet or more back from the ordinary high water mark of lakes or from the bank of a stream.

s. 236.20 (2) (b), Wis. Stats. Existing monuments that are archival and accepted as correct should not be removed and reset even if they do not comply with the standards of s.236.15 (1), Wis. Stats. They are noted as "existing" or "found" and described by type, diameter, material, etc.

Monuments must be set, or found and accepted, at the true corner locations; it is not permissible to show set or accepted monuments as being "off line". If the deed or other recorded description does not agree with the found monument location, then show the "recorded as" bearing and distance between the monument, along with that measured.

s. 236.15 (1) (h), Wis. Stats. All subdivision exterior boundary monuments must be set prior to submittal of the plat. The primary approval authority may grant a **temporary waiver for placing interior monuments.** The subdivider provides a surety bond to ensure that the monuments will be set within the time designated.

s. 236.15 (1)(ag),(b), Wis. Stats STANDARDS

Exterior boundary, interior block/ROW corner monuments:

Minimum: Length: 18" Weight: 3.65 lbs./lin.ft **Typical:** 2" o.d. x 18" iron pipe, 3.65 lbs/lin ft

1 1/4" x 18" iron bar, 4.17 lbs/lin ft 1 1/4" x 18" iron re-bar, 4.30 lbs/lin ft 5" dia. concrete w/ imbedded ferrous rod 4" sq. concrete w/ imbedded ferrous rod

Lot/outlot, public dedication, meander corner monuments:

Minimum: Length: 18" Weight: 1.13 lbs./lin.ft

Typical: 1" o.d. x 18" iron pipe, 1.13 lbs/lin ft

3/4" x 18" iron bar/rebar, 1.50 lbs/lin ft

Any size or shape ferrous bar or pipe that meets the minimum length and weight requirements is acceptable.

Any durable metal or concrete monument may be used, provided they have an embedded permanent magnet near the top, and are uniform throughout the platted area.

Note that the above are minimum requirements. The Surveyor must exercise judgment when conditions warrant the use of longer or larger monuments to ensure that the monuments are retraceable.

MONUMENT WAIVERS

When strict compliance with the monumentation requirements is unduly difficult, the Surveyor may request a waiver of the requirements.

- To obtain a waiver, the Surveyor must submit a request in writing to Plat Review along with the plat. The request must include:
- Reference to the statutory requirement to be waived.
- The location of the affected corners.
- The reason(s) negating use of standard monumentation.
- The proposed alternative monumentation.

Plat Review will grant or deny the request, or may propose other alternative monumentation. The grant of waiver should be noted on the plat, and will be included in our final Certification letter.

s. 236.15 (1)(c),(d), Wis. Stats

s. 236.15 (1)(f), Wis. Stats

s. 236.15 (1)(g), Wis Stats

s. 236.15 (1)(g), Wis. Stats

MONUMENT WAIVERS

When strict compliance with the monumentation requirements is unduly difficult, **Plat Review may make other reasonable requirements**. The alternative must be sufficient for the exact retracement of the boundaries affected. Some examples are:

Condition:	Alternative Monumentation:
Corner falls in sidewalk, curb, or	Chiseled "X", Magnetic or P.K. nail,
pavement.	Drill Hole
Corner falls in bedrock or rock	Chiseled "X" or drill hole.
outcropping.	
Corner occupied by tree or other	Standard monuments, offset from
feature	corner on each line.
Corner occupied by building.	Standard monuments, set off line
	as witness corners. In some cases,
	the building corner is used to mark
	the boundary corner.

Plat Review can not waive the monument requirements for reasons of inconvenience (ex: corner occupied by moveable debris, corner in unharvested field, corner in thicket, etc.).

EXAMPLES RELATED TO THIS SECTION

Monument Waiver Request Form

Monument Waiver Grant Letter

Monument Properties Tables

US Public Land Survey Monument Record

Interior Monument Waiver

Request for **Monument Waiver**

Plat Review

Plat Review – DOA

Shipping Address: 101 E Wilson St FL 9

Madison WI 53703

Mailing Address: PO Box 1645

Madison WI 53701

Phone: 608-266-3200 **Fax:** 608-264-6104 **Email:** plat.review@wi.gov

Department of Administration	Web: http://doa.wi.gov/platreview
Subdivision Name or other map reference:	Treat in particular in particular in the particu
County:	
Location: Section , T N, R , of	
Survey Prepared For:	
Surveyor, Company & Shipping Address:	
Name:	
Company:	
Shipping Address:	
Phone:	
Fax:	
Email:	
Date:	
1. Identify affected corners (e.g. "NE corner lot 1" or "Oak Roa	
Describe conditions that prevent standard monumentation (right-of-way"):	
Describe proposed alternate monumentation (e.g. "Chiseled on line"):	d X in concrete" or "3/4" x 18" rebar, offset to east

4. Include map.	
5. Include any additional information.	
Request Approved by:	
Comments:	
MONUME	NT WAIVERS
	rements of s. 236.15 (1) (a, b, c, or d), Wis. Stats., is unduly
difficult, Plat Review may make other reasonable re	quirements as allowed for by <u>s. 236.15 (1) (g), Wis. Stats.</u>
	racement of the boundaries affected. Some examples are:
Condition:	Example Alternative Monumentation:
Corner falls in sidewalk, curb, or pavement.	Chiseled "X", Magnetic or P.K. nail, Drill Hole. Chiseled "X" or drill hole.
Corner falls in bedrock or rock outcropping. Corner occupied by tree or other feature.	Standard monuments, offset from corner on each line.
Corner occupied by building.	Standard monuments, offset from corner on each fine. Standard monuments, set off line as witness corners. In
Corner occupied by building.	some cases, the building corner may be used as the
	boundary corner.
Corner falls on centerline or within road right-of-	Spike, Magnetic or P.K. nail. Monumentation within right-
way. (no waiver required on subdivision or	of-way be waived entirely if right of way lines are
County plats)	properly monumented on CSM's and other maps.
County pians)	property monumented on Conto and onler maps.
Plat Paviaw can not waive the monument requirements	for reasons of inconvenience (av. corner occupied by
Plat Review can not waive the monument requirements moveable debris, corner in thicket or wetlands, etc.).	s for reasons of inconvenience (ex. corner occupied by
moveable debits, collict in unexet of wettailus, etc.).	

Sample Monument Waiver Grant Letter



JAMES E. DOYLE
GOVERNOR
MICHAEL L. MORGAN
SECRETARY
Plat Review
101 E. Wilson St FL 9, Madison, Wisconsin 53703
PO. Box 1645, Madison WI 53701
(608) 266-3200 Fax: (608) 264-6104

E-mail: <u>plat.review@wi.gov</u> http://doa.wi.gov/platreview

March 22, 2004

STANLEY J. KING BLACKHAWK ENGINEERING, LTD.. 2 INSIGHT DRIVE PLATTEVILLE, WI 53818

Subject: QUALITY WOOD TREATING CSM

FARM LOTS 38 AND 39

CITY OF PRAIRIE DU CHIEN, CRAWFORD COUNTY

Dear Mr. King:

You have requested a waiver of the requirement of s. 236.15 (1) (c) that 1" diameter by 18" length iron pipe (or permitted equivalent) monuments be set at all Certified Survey Map (CSM) lot corners. You have proposed using a "P.K. nail" in lieu of the standard monument at the NE corner of lot 2, as the corner falls on concrete pavement as indicated on the CSM.

As allowed under s. 236.15 (1) (g), we agree with the proposed monumentation, and waive the requirement of s. 236.15 (1) (c) for the NE corner of lot 2. The proposed monumentation provides for adequate retracement of the corner; strict compliance with this section would be unduly difficult.

We suggest that you reference this grant of waiver on the CSM. If there are any questions concerning this waiver or preparation of the CSM, please contact our office at the number listed above.

Sincerely,

Don Sime Plat Review

Monument Tables				
WEIGHTS OF SQUARE & ROUND IRON BARS				
Thickness or diameter in inches	Weight of square bar 1 ft. long	Weight of round bar 1 ft. long		
1/16	.013	.010		
1/8	.053	.042		
3/16	.119	.094		
1/4	.212	.167		
5/16	.333	.261		
3/8	.478	.375		
7/16	.651	.511		
1/2	.850	.667		
9/16	1.076	.845		
5/8	1.328	1.043		
11/16	1.608	1.262		
3/4	1.913	1.502		
13/16	2.245	1.763		
7/8	2.603	2.044		
15/16	2.989	2.347		
1	3.400	2.670		
1 1/16	3.838	3.014		
1 1/8	4.303	3.379		
1 3/16	4.795	3.766		
1 1/4	5.312	4.173		
1 5/16	5.857	4.600		
1 3/8	6.428	5.049		
1 7/16	7.026	5.518		
1 1/2	7.650	6.008		
1 9/16	8.301	6.520		
1 5/8	8.978	7.051		
1 11/16	9.682	7.604		
1 3/4	10.410	8.178		
1 13/16	11.170	8.773		
1 7/8	11.950	9.388		
1 15/16	12.760	10.020		

Sizes and Weights of Reinforcing Bars			
Bar No.	Size, diameter, inches	Weight, lb. Per ft.	
2	1/4	0.167	
3	3/8	0.376	
4	1/2	0.668	
5	5/8	1.043	
6	3/4	1.502	
7	7/8	2.044	
8	1.0	2.670	
9	1.128	3.400	
10	1.270	4.303	
11	1.410	5.313	

IRON PIPE					
	DIMENSIONS				
Weight per Foot lb.					
Nom. Dia. Inches	Outside Dia. Inches	Inside Dia. Inches	Plain Ends	Thread & Cplg.	
1/8	.405	.269	.24	.25	
1/4	.540	.364	.42	.43	
3/8	.675	.493	.57	.57	
1/2	.840	.622	.85	.85	
3/4	1.050	.824	1.13	1.13	
1	1.315	1.049	1.68	1.68	
1 1/4	1.660	1.380	2.27	2.28	
1 1/2	1.900	1.610	2.72	2.73	
2	2.375	2.067	3.65	3.68	
2 1/2	2.875	2.469	5.79	5.82	
3	3.500	3.068	7.58	7.62	
3 1/2	4.000	3.548	9.11	9.20	
AME	AMERICAN INSTITUTE OF STEEL CONSTRUCTION				

December 2014

Blank Page


U. S. PUBLIC LAND SURVEY MONUMENT RECORD

INSTRUCTIONS:

This record shall show the location of the corner and shall include all of the following nine elements (a through i).

(a) Identify the corner by reference to the U.S. public land survey system.

O = Corner monument restored.



(b) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

(c) In the plan view drawing below, provide reference ties to at least 4 witness monuments, or, if the location is within a municipality, to at least 2 witness monuments. (Witness monuments shall be made of concrete, natural stone, iron or other equally durable material.)

Describe witness monuments.

(d) Show a plan view drawing depicting the relevant monuments and reference ties which is sufficient in detail to enable accurate relocation of the corner monument if the corner monument is disturbed. Indicate north.

(e)	by distance a above. Show and (1) the c	material discrepa d and the location and direction. Sh the distances bet corner as restored own on the drawing	of that corner ow the discrepa ween the corner or reestablish	as previously a ncy on the plan as previously a ed and (2) to a	restored or reesta view drawing unde restored or reesta	blished r (d),
(f)	Was the corne found perpetu	r restored through	n acceptance of	(1) an oblitera	ted evidence loca	tion, or, (2) a
{ g&h	method, incl	er reestablished t uding the directio used for proportio	ons and distance	s to other publ	ic land survey co	o, show the rners used as
					Affix I	and Surveyor Sea
, (i)	I, (type or print	name) certify tha	at the corner lo	ocation shown		
	on this record	was determined by at this U.S. Publimplete to the best	v me or under my	/ direction and	is !	

Date

Signature

EXAMPLE INTERIOR MONUMENT WAIVER

SUBDIVISION MONUMENT PLACEMENT WAIVER REQUEST

This is a waiver request for monument placement requirements per s.236.15 of the Wisconsin Statutes and Chapter 17-12(e) of the Village of Harrison Subdivision Code.

Exterior boundary monuments have been set, but interior monuments for Lots 21 through 40 in the plat of Kambura Acres II, Village of Harrison, Calumet County, Wisconsin, will not be monumented due to extensive grading to prepare the site for construction. These Lots will be monumented after grading is complete and a monumentation certification will be provided to the Village of Harrison. No building permits will be issued for these lots prior to the monumentation certification.

All monuments shall be in place within one (1) year of the recording of the plat of Kambura Acres II. \$1000.00 dollars will cover the cost of Martenson & Eisele, Inc. to complete the plat staking.

APPLICANT				
Signature Wallace Bud Ruseh				
Printed NameBud Rusch				
Company NameRusch Development Properties, LLC				
Address W6132 Shagbark Hickory Lane, Menasha WI 54952				
Telephone 920-733-1646				
Date 10-26-2016				
APPROVED BY (Village of Harrison)				
Signature Mu/uu				
Printed Name / Mark J. Mommaents				
Title Planner				
Department Planning				
Date 10-27-2016				